



## VISUAL STANDARD

# Storage



- Security of materials during storage and movement must be suitable to prevent fall.
- Materials should be stacked horizontally if vertical straps should be used to prevent fall.
- Storage through racking and shelving should be used widely across the project by supply chain.
- Materials should be stored as per manufacturers recommendations.



## KEY POINTS

- Materials are stored so they are not at risk of injuring people or being damaged.
- Access around storage is suitable for people and plant movement.
- Access to storage areas is restricted with only competent people allowed to move materials to other areas of work
- All materials SWL are noted on RAMs with control measures.