



VISUAL STANDARD

Deliveries



Ensure that delivery of material is planned to:

- Receive knowing you have sufficient areas to store.
- Loads are mechanically offloaded to save time.
- Loads are checked on arrival for quality and that storage is also suitable to protect materials.



KEY POINTS

- Plan movement of materials from manufacture to installation.
- Develop of site manufacturing
- Vertical lifting by mechanicals means with certified lifting.
- Minimise manual handling horizontal distribution by mechanical
- Plan Waste removal routes as you would delivery of material
- Only competent plant operators and lifting teams used.
- Develop exclusion zones to protect people through project life
- Develop best practice with engine idling stop when parked.